CO PFH 123-1(1) Sample Project Road AMENDMENT A002 REVISED 04/27/09

Section 208. - STRUCTURE EXCAVATION AND BACKFILL FOR SELECTED MAJOR STRUCTURES Show ame

Show amendment number and revision date.

Measurement

208.13 Delete the text and substitute the following:

Measure the Section 208 items listed in the bid schedule according to Subsection 109.02 and the following.

Measure foundation fill by the cubic yard in place for rockeries and MSE walls (where placement is directed by the CO). Limit the volume measured to that placed inside vertical (and sloping) planes as shown on the plans. Use these planes to determine pay quantities regardless of the amount of material placed outside these planes.

Measure temporary shoring by the lunp sum for each individual retaining wall. Measure temporary shoring only for shoring required to maintain one 10-foot lane plus temporary barrier.

Do not measure foundation fill at concrete walls for payment.

Use strikethrough for deleted text.

Show revised text with italic font.