


LENGTH AND SPACING TABLE						
APPROACH SPEED*	BUFFER SPACE LENGTH	CHANNELIZING DEVICE			CONCRETE BARRIER FLARE RATE	WORK ZONE CLEAR ZONE WIDTH FEET
		TAPER AREA	BUFFER SPACE	WORK SPACE		
MPH	FEET	SPACING IN FEET				
20	115	20	40	40	1:8	10
25	155	20	50	50	1:8	10
30	200	20	60	60	1:8	10
35	250	20	70	70	1:9	10
40	305	20	80	80	1:10	15
45	360	20	90	90	1:12	20
50	425	20	100	100	1:14	20
55	495	20	110	110	1:16	20
60	570	20	120	120	1:16	30
65	645	20	130	130	1:16	30
70	730	20	140	140	1:16	30

* Approach speed based on the regulatory posted speed, not the advisory speed.

NOTES:

1. Install signs and other devices for single lane closure according to Details ET 635-6, 7, 8, or 9.
2. Final location and spacing of traffic control devices may be changed to fit field conditions as approved by the CO.
3. Use minimum width shown unless otherwise specified in Section 156.
4. Place barrier according to the AASHTO Roadside Design Guide. Terminate barrier ends outside the work zone clear zone or protect the barrier ends with a crash cushion. Include reflectors on barrier at 25-foot intervals.
5. Place channelizing devices at downstream taper during non-work hours or when access is not needed.
6. Do not allow equipment, materials, or vehicles to be parked or stored in the buffer space.
7. Reduce or eliminate channelizing devices and barrier in downstream taper if necessary to provide access to work space.



U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION OFFICE OF FEDERAL LANDS HIGHWAY	
EFLHD DETAIL	
TEMPORARY TRAFFIC CONTROL SINGLE LANE CLOSURE LAYOUT (WITH TEMPORARY BARRIER)	
STANDARD APPROVED FOR USE 6/2005 REVISED: 6/2015 3/2016 9/2019 9/2020	DETAIL ET 635-13

NO SCALE