


TYPICAL APPLICATION: ONE WAY, TWO LANE ROADWAY, CLOSING PARTIAL LANE AND SHOULDER USING TEMPORARY BARRIER



NOTES:

1. Final location and spacing of temporary traffic control devices may be changed to fit field conditions as approved by the CO.
2. Place barrier according to the AASHTO Roadside Design Guide, latest edition. Terminate barrier ends outside the clearzone or protect the ends of barrier with a crash cushion. Mount reflectors on barriers at 25-foot intervals.
3. Repeat signs on both sides of the roadway.
4. Use minimum width shown unless otherwise specified in Section 156.

LENGTH AND SPACING TABLE					
APPROACH SPEED*	MINIMUM TAPER LENGTH	BUFFER SPACE LENGTH	CHANNELIZING DEVICE		
			TAPER AREA	BUFFER SPACE	WORK SPACE
MPH	FEET	FEET	SPACING IN FEET		
20	Shifting taper formula: $L = \frac{WS^2}{120}$ for $S \leq 40$ MPH $L = \frac{WS}{2}$ for $S \geq 45$ MPH	115	20	40	40
25		155	25	50	50
30		200	30	60	60
35		250	35	70	70
40	Where: L = Minimum length of taper W = Width of offset in feet S = Numerical value of posted speed limit or 85 percentile speed prior to work in miles per hour	305	40	80	80
45		360	45	90	90
50		425	50	100	100
55		495	55	110	110
60		570	60	120	120
65		645	65	130	130
70	730	70	140	140	

* Approach speed based on the regulatory posted speed, not the advisory speed.

SIGN SPACING TABLE			
ROAD TYPE	DISTANCE BETWEEN SIGNS IN FEET		
	A	B	C
Urban and Rural 30 MPH and less	100	100	100
Urban and Rural 35 MPH to 50 MPH	350	350	350
Rural greater than 50 MPH	500	500	500
Expressway / Freeway	1000	1500	2640

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
EASTERN FEDERAL LANDS HIGHWAY DIVISION

U.S. CUSTOMARY DETAIL

**TEMPORARY TRAFFIC CONTROL
ONE WAY, TWO LANE ROAD
SHOULDER WORK WITH MINOR
ENCROACHMENT (WITH BARRIER)**

DETAIL APPROVED FOR USE

APPROVED: MAY 2011
REVISED: NOVEMBER 2022I

DETAIL
E635-10